

Project Name: 中山希尔顿酒店



Sheet Title: 三层灯具表

Issue Date: 2011/10/27

Revision Date: 2011/10/27

| 区域 Zoning | 编号 Code | 品名 Discription | 光源 Light Source | 电压 (V) Voltage | 功率 (W) Unit Watts | 单位 Units | 三层 | 总功率 Total Load | 品牌型号 Brand & Series | 备注 Remarks |
|--------------|------------|--|--------------------|-------------------|----------------------|-------------|-----|-------------------|-------------------------|---------------|
| 三层公共区域 | LL1 | LED灯带 LED Strip Light | LED 10W/M/2300K | 24 | 10 | m. | 376 | 3760 | LUCI POWER FLEX CLFT 10 | |
| | LL2 | LED灯带 LED Strip Light | LED 6W/M/2300K | 24 | 6 | m. | 196 | 1176 | LUCI POWER FLEX CLFT 10 | |
| | DL2 | 嵌入式筒灯 Recessed Downlight | MR16 50W/FL | 12 | 50 | ea. | 40 | 2000 | SKYLUX SK-2821 | |
| | DL3 | 嵌入式筒灯 Recessed Downlight | MR11 35W/FL | 12 | 35 | ea. | 22 | 770 | SKYLUX SK-2805 | |
| | DL6 | 下照灯 | LED 3 W | 24 | 3 | ea. | 29 | 87 | | |
| | AL3 | 嵌入式可调筒灯 Recessed Adjustable Downlight | MR16 50W/FL | 12 | 50 | ea. | 63 | 3150 | SKYLUX SK-2822 | |
| | AL4 | 嵌入式可调筒灯 Recessed Adjustable Downlight | MR16 50W/FL | 12 | 50 | ea. | 97 | 4850 | SKYLUX SK-2822 | |
| | AL7 | 嵌入式可调筒灯 Recessed Adjustable Downlight | MR16 50WX2/FL | 12 | 100 | ea. | 112 | 11200 | SKYLUX SK-9501 | |
| | AL9 | 嵌入式筒灯 Recessed Downlight | MR11 35W/FL | 12 | 35 | ea. | 79 | 2765 | | |
| | UL1 | 地埋灯 | LED 3 W | 24 | 3 | ea. | 105 | 315 | | |
| | WL1 | 水池灯 | LED 3 W | 24 | 3 | ea. | 8 | 24 | AD 1613530.000 | 嵌入式安装 |
| | | 吊灯 | 预留电源 2000W | 220 | 2000 | ea. | 2 | 4000 | 由室内设计师决定 | |
| | | 吊灯 | 预留电源 1000W | 220 | 1000 | ea. | 1 | 1000 | 由室内设计师决定 | |
| | | 吊灯 | 预留电源 800W | 220 | 800 | ea. | 1 | 800 | 由室内设计师决定 | |
| | | 吊灯 | 预留电源 500W | 220 | 500 | ea. | 2 | 1000 | 由室内设计师决定 | |
| | | 吊灯 | 预留电源 60W | 220 | 60 | ea. | 29 | 1740 | 由室内设计师决定 | |
| | | 落地灯 | 预留电源 60W | 220 | 60 | ea. | 12 | 720 | 由室内设计师决定 | |
| | | 灯柱 | 预留电源 100W | 220 | 100 | ea. | 5 | 500 | 由室内设计师决定 | |
| | | 台灯 | 预留电源 60W | 220 | 60 | ea. | 2 | 120 | 由室内设计师决定 | |

39977 W

- Notes:
- 1、灯具尺寸以实际样品为准。
 - 2、TS长度分为600mm/900mm/1200mm，安装时需要交叠以避免产生阴影。
 - 3、承包商需提供样品及施工详图以供审核。